

CONSTRUCTION OF ACESS ROAD AT NO.1 FREDRICK ILEKHUOBA CLOSE, OFF BOUNDARY ROAD - BENIN CITY					
S/N	DESCRIPTION OF ITEM	QTY	UNIT	U/PRICE	AMOUNT
1	<b><u>DRAINAGE</u></b>				
	<b><u>Excavating and Filling</u></b>				
	<b><u>Excavation:</u></b>				
a	Bulk excavation; commencing from ground level; not exceeding 1.5m deep; drainage trenches.	326.25	m <sup>3</sup>		-
	<b><u>Insitu concrete</u></b>				
	<b><u>Concrete Grade 15</u></b>				
b	Blinding works for the drainage : Not exceeding 50 mm thickness for the blinding works.	24	m <sup>3</sup>		-
					-
					-
	<b><u>Masonry</u></b>				-

					-
	<b>Block walling</b>				-
c	Walls;230mm thick;blockwork; laid in straitcher bonding, cement mortar (1:6); filled solid with concrete concrete grade 7	696	m <sup>2</sup>		-
					-
	<u>15mm thick cement and sand (1:3)</u>				
d	Rendering on walls internal and external	696	m2		
e	<b>Fence coping works</b>				
g	Ditto: Casting of concrete wall copplings on 225 mm block work with forwork with formwork costed together	1	sum		-
	<b>Drainage works to Summary:</b>				-
<b>S/N</b>	<b>DESCRIPTION OF ITEM</b>	<b>QTY</b>	<b>UNIT</b>	<b>U/PRICE</b>	<b>AMOUNT</b>
2	<b><u>CARRIAGEWAY</u></b>				
	<b><u>Excavating and Filling</u></b>				
	<b><u>Site preparation</u></b>				



1	Drainage				-
2	Carriage way				-
	Sub-Total				-
	Add Contigency				-
	GRAND TOTAL				-