

SEME KRAKE COMMAND CONSTRUCTION

DESCRIPTION	QUANTITY	UNIT	UNIT	TOTAL COST
			COST	NGN
PEDESTRIAN PROCESSING BATTERY COVERING (8mx1.5m x 2 units)				
provide and install 5.3x1.2m fabricated water proof aluminum grilled covering with openings(as shown in picture) fixed 250mm above natural ground level	14.36	sq.m		
Donpalon covering with clips along the edges	32.60	sq.m		
sub total				
SERVER ROOM (INSIDE THE MAIN CONTROL OFFICE)				
Provide 600mmx600mm raised floor with 50mm	23.50	sq.m		
Provide and install aluminum partitioning wall with 8mm glazed top 1200mmx900mm	35.31	sq.m		
Provide and install Aluminum door with automatic closer attached to partition	1.00	Nr		
Finishes (bolts, nuts, fasteners, washers, strip rubber for aluminum works)	1.00	Ls		
SECONDARY INSPECTION CUBICLE (CHECKROOM)				
Install 6.7m x 4.5m x 3.3m aluminum partition and 900mm x 2100mm door	1.00	Ls		
supply and install 1x2 workstation	1.00	Nr		
Supply and install approved ergonomic office chairs	2.00	Nr		

Battery Room (Main Office)				
Provide and install aluminum partitioning wall with 8mm glazed top 1200mmx900mmx3000mm	28.51	sq.m		
Provide and install Aluminum door with automatic closer attached to partition	1.00	Nr		
Finishes (bolts, nuts, fasteners, washers, strip rubber for aluminum works)	1.00	Ls		
SUMMARY				
PEDESTRIAN PROCESSING BATTERY COVERING (8mx1.5m x 2 units)				
SEVER ROOM				
SI CHECKROOM				
Battery Room (Main Office)				
GRAND TOTAL				
Pedestrian checking area: this has Arrival and Departure cubicles				

