

REHABILITATION OF FENCE @ SEYP SHELTER, OREDO LGA- EDO STATE.

Total meter is = 104 m

S/N	DESCRIPTION OF ITEM	QTY	UNIT	U/PRICE	AMOUNT
İ	ELEMENT NO. 1: PRELIMINARIES				
а	Allow for the mobilization and demolization of equipment on site		sum		0
Ĭ.	A HOLLING HIGH HOUSE EARLY AND GOLD HOLD HOLD HOLD HOLD HOLD HOLD HOLD H		oum		S
b	Allow for the carefull demolition of the existing fence measuring 88				
	.53 m2 and cart away debris off site		sum		-
	Preliminaries & Demolition to Summary:				N -
	,				
1	ELEMENT NO. 2: BLOCK WORK AND FINISHING				
i I	BLOCK WORK				
	Hollow sandcrete block laid in stretcher bond with cement and sand (1:4) mortar				
а	Additional course on existing fence: 225 x 225 x 450 mm walls	47.61	m2		0
b	Ditto: Left side elevation of the fence build up	73.5	m2		0
С	15mm thick cement and sand (1:3) Rendering on walls internal and external	468	m2		0
d	Casting of fence coppings 75 mm-100 mm thick concrete with				
u	formwork all costed togther	2.392	m		0
	PAINTING/CLEAR FINISHING				
	Painting Works Painting to wall shall be measured in square meters. Paint shall be				
	supplied to site in seal containers and approved by the engineer. The rate shall include supply of all materials, workmanship, surface				
	preparations by applying 3-5mm thickness of plaster of paris screed on the walls, protection of painted surfaces.				
е					
	One undercoat and two coat coloured finishing coats of fine coat emulsion paint for internal and external walls of fence.	468	m2		-
	emusion paint tot internal and external walls of ferice.	100	2		
	Block work and Finishings to Summary:				-
	ELEMENT NO. 3: FENCE METALS & OTHER WORKS				
	FENCE METALS WORKS Concertina Razor Wire				
a	installation of concertinia razor wire (Double) with its hooks and				
	hanger installations works	104	m		-
b	Allow for the fabrication and installation of double swing metalic gate				-
	made of 2mm with its stoper with all priming and painting according to instruction of the engineer. 4000 mm x 3000 mm height with				
	approved design.	1	nr		-
Ī	Interlocking				
	Interlocking Pavement - External Works Imported filling				
	· · · · · · · · · · · · · · · · · · ·	1			

С	Imported filling, sharp sand /stone dust bed not exceeding 75mm thick, level and to fall in preparation to receive pavement works	298	m²	-	
d	$200\ mm\ x\ 100\ x\ 50\ mm$ thick machine vibrated Interlocking bricks, pavings, level to fall only, including filling gaps with stone dust in approved pattern and colours . Well compacted and level with approved filled marerials and sloped to ensure surface run water out of the compound.	298	m^2	-	
e I	<u>Kerbs</u> Supply and installed kerbs- 600 x 100 mm x 150 mm	104	m	-	
f	Allow for the painting of kerbs	47	m	-	
	To Collection			-	
	SUMMARY				
1	Preliminaries & Demolition			₩ -	
2	Block work and Finishes			₩ -	
3	Metal Works			₦ -	
	Sub-Total			₩ -	
	ADD Contigencies				
	GRAND TOTAL			N -	
	TOTAL USD			\$ -	