

DAMBOA MONDAY MARKET SCOPE OF WORK

Scope of work for Damboa Monday Market	
S/N	Description of work
A	
1	Removing and reconstruction of all roof members to gable end roof in all the six blocks
2	Installation of aluminium roofing sheet of 0.55M thickness in all the six blocks
3	Block work to build up existing collapsed walls
4	Construction of internal and external noggings in all the six blocks
5	Introduction of pillars to support roof members
6	Replacement of damaged doors in all the six blocks
7	Laying of batten along the gable end of all the six blocks
8	Laying and replacement of ceiling board in all the six blocks
9	Fixing of ceiling fans in all the 104 shops
10	Floor screeding and floor maintenance in all the six blocks
11	Laying of electrical conduits, pipes, bulbs, wall brackets, sockets, wiring of all the shops
12	Cleaning around the construction site for a healthy environment
13	Construction of columns and block work along the corridor work
14	Selection of cash for work beneficiaries

OK

the six block

the six block