

Updated Improved Emergency Shelter (Dikwa Type)

S. No.	Item	Quantity	Unit	Unit Cost (NGN)	Total Cost (NGN)	Unit Cost (USD)	Total Cost (USD)	Remarks
	Plastic Sheeting:							
1	Plastic Sheeting - finish size 4mx60m, reinforced bands along edges, aluminium reinforced, labeled with IOM Logo	0.33	Roll		To be provided by IOM			
	Sub-Total				0.00		0.00	
	Construction Materials and Labour:							
1	CGI Sheet (6 feet long - 0.20mm thick)	36.00	Sheets		0.00	0.00	0.00	
2	GI Plain sheet for ridge cover (12 feet x 0.15mm thick)	2.00	Pcs		0.00	0.00	0.00	
3	2" x 4" x 12' Timber poles - full length	23.00	pcs		0.00	0.00	0.00	
4	2" x 3" x 12' Timber poles - full length	64.00	pcs		0.00	0.00	0.00	
5	2" x 2" x 12' Timber poles - full length	19.00	pcs		0.00	0.00	0.00	
6	1" x 4" x 12' timber fascia boards - full length	7.00	pcs		0.00	0.00	0.00	
7	Timber battens	1.50	Bundle		0.00	0.00	0.00	
8	Door hinges	2.00	Pair		0.00	0.00	0.00	
9	Door latches (Inside)	2.00	Pair		0.00	0.00	0.00	
10	Door latches (outside)	1.00	Pair		0.00	0.00	0.00	
11	Window hinges	4.00	Pair		0.00	0.00	0.00	
12	Window towel bolts	4.00	Nos		0.00	0.00	0.00	
13	Langalanga	23.00	Nos		0.00	0.00	0.00	
14	4 inches timber nails	8.00	Kg		0.00	0.00	0.00	
15	3 inches timber nails	6.00	Kg		0.00	0.00	0.00	
16	1 1/2 inches timber nails	5.00	Kg		0.00	0.00	0.00	
17	Roofing nails	2.00	Packets		0.00	0.00	0.00	
18	Mansonary Block Work	44.00	pcs		0.00	0.00	0.00	
19	Cement, standard 50kg bag	3.00	Bags		0.00	0.00	0.00	2 Bags for foundation footing, 1 bag for block work
20	Sharp sand	0.25	CuM		0.00	0.00	0.00	0.125 CuM for foundation footing, 0.125 CuM for Block work
21	Aggregate	0.25	CuM		0.00	0.00	0.00	0.125 CuM for foundation footing, 0.125 CuM for Block work
22	Approved laterite fill compacted	6.00	CuM		0.00	0.00	0.00	
23	Anti termite treatment (4 liters can)	0.50	Can		0.00	0.00	0.00	
24	Used engine oil	8.00	Litres		0.00	0.00	0.00	
25	Labour	1.00	Item		0.00	0.00	0.00	
26	Transportation	1.00	Item		0.00	0.00	0.00	
	Sub-Total				0.00		0.00	
	Total Cost for 1 Shelter				0.00		0.00	

