BILL OF QUANTITY FOR HH SHOWER

Item	Description	Unit	Qty	Rate (NGN)	Total Amount (NGN)
	Site clearance; clear site of grass, shrubs and				
Α	bushes etc	Item	1		
	Prepare ground and compact hardcore of 150mm				
В	insitu	m^3	3.6		
	Cast insitu plain concrete, thickness 75mm, mix,				
С	cement:sand:aggregate(1:2:4)	m^3	0.135		
	Costruct 150mm thick Mud brick wall, height not				
D	exceeding 2500mm, in cement sand mix 1:4	m^3	9.87		
	Soak pit of 100x100x100mm, filled with hardcore				
	with a drain pipe from the slab into the soak pit				
Е	outside the structure. (refer drawing)	m ³	0.001		
	ROOF				
	Provide and fix soft wood timber wall plate size				
F	4"x2", well fastenned to the wall with hoop iron	LM	2.8		
	Provide and fix soft wood timber roof truss, size				
G	4"x2"	LM	6		
Н	Provide and fix roof purlins, size 3"x2"	LM	6		
	Provide and fix long precoated corrugated				
	galvanised iron sheets, gauge 30. 0.2mm thick,				
I	1.8x 0.6m wide.	PCS	3		
	Provide and install CGI sheet framed doors fixed				
	with all assesories, lockable from both interior and				
l,	lexterior	Pc	1		
J	Sub total	1 0	1		0
	Add VAT			0	0
	Grand Total			0	0
	Grana Total				U